

1.14.11 Category J: Decanter Centrifuge

1.14.11.1 Scope of Supply

General Data:

Below are the Specifications and Schedule of Particulars and Guarantees for the supply of one (1) dewatering centrifuge which will be located in the existing sludge treatment room. The design flow is 80 m³/h with 3.5% solids concentration.

Please note that the WWTP's controllers are of "Modicon". Any equipment that will be supplied to Ayalon WWTP shall fully comply with the plant's controllers.

Tag Numbers: M-800.

| Component | Number of Units | Bidder Confirmation |
|----------------------------------|-----------------|---------------------|
| Decanter centrifuge | 1 | |
| Service pedestal | 1 | |
| MCC | Excluded | |
| PLC | Included | |
| Solids Diverted Gate | Included | |
| <u>Submittals</u> | | |
| Electrical drawings format dwg. | 2D | |
| Machine drawing format rvt./ifc. | 3D | |

1.14.11.2 Specifications

| Item | Minimum requirement | Guaranteed value |
|--|---|------------------|
| <u>General</u> | | |
| Manufacturer | Flottweg, Alfa Laval, Andritz, GEA or approved equivalent | |
| <u>Model</u> | X7E or approved equivalent | |
| Flow Design, m ³ /hr | 80 | |
| Solids Load, kg/hr | 2,800 | |
| Working days/week | 5.5 | |
| Hours per Shift | 8 | |
| Sludge type | Anaerobic digested | |
| Feed Sludge Solids Concentration, % | 3.5% | |
| Feed Sludge VSS/TSS | 70% | |
| Dewatered sludge Solids Concentration @ design flow and solids load, % | 22 | |

| Item | Minimum requirement | Guaranteed value |
|--|------------------------------------|------------------|
| Solids Capture rate @ design flow and solids load, % | 97 | |
| Counter or Co-current | | |
| Working Point | Continuously at maximum speed | |
| Energy recovery | Flottweg “Recuvane” or equivalent. | |
| <u>Bowl</u> | | |
| Bowl type | Super deep pond | |
| Bowl volume, lit | 700 | |
| Bowl Speed, rpm | 2,920 | |
| Operating G force, G | 3,000 | |
| G Volume m ³ · rpm | 2,730 | |
| Bowl Material | Duplex | |
| Material long. bowl strips | SS316 | |
| Bowl internal diameter, mm | 700 | |
| Diameter/length ratio | 4 | |
| Cone angle | 18° | |
| <u>Scroll</u> | | |
| Scroll Speed, rpm | | |
| Scroll Material | SS316 Ti/SS316L | |
| Range of Operating Diff. Speeds, RPM | 0-10 | |
| Wear Surfaces Material of: | | |
| Tip edges of scroll | Tungsten Carbide | |
| Leading edges scroll | | |
| Sludge feed ports | Replaceable bushings | |
| Sludge outlet ports | Replaceable bushings | |
| Guaranteed life of all wear surfaces (between rebuilds and/or replacements), h | | |
| Nom. Scroll torque, Nm | 40,000 | |
| <u>Other materials</u> | | |
| Wetted pars | SS316Ti/SS316L | |
| Non-wetted parts | Carbon steel, painted. | |

| Item | Minimum requirement | Guaranteed value |
|--|---------------------|------------------|
| <u>Bearings</u> | | |
| <u>Main Bearings</u> | | |
| Type | | |
| L-10 life, h | | |
| Method of Lubrication | Automatic Grease | |
| <u>Scroll Conveyor Bearings</u> | | |
| Type | | |
| L-10 life, h | | |
| Method of Lubrication | | |
| <u>Thrust Bearings</u> | | |
| Type | | |
| L-10 life, h | | |
| Method of Lubrication | | |
| Backdrive System | | |
| <u>Electrical Motor</u> | | |
| Manufacturer | | |
| Type or Model | | |
| Explosion proof standard | Unclassified | |
| Motor Speed, RPM | | |
| Motor Rating, HP | | |
| Motor IP Rating | IP 55 | |
| Service Factor | | |
| Pwr Fctr Full Load | | |
| Eff. at Full Load, % | | |
| Current: | | |
| Nominal AMP | | |
| Locked Rotor AMP | | |
| Insulation Class | | |
| Temperature Rise @ Full load C° | | |
| Net Weight Motor, kg | | |
| Pump Type | | |
| Reservoir Volume, l | | |
| Insulation Class | F | |

| Item | Minimum requirement | Guaranteed value |
|---------------------------------------|--------------------------------------|------------------|
| Temp Rise Full Load C° | | |
| Net Weight Motor, kg | | |
| <u>Protections</u> | | |
| Overload protection | Included | |
| Overheat protection | Included | |
| Vibration Protection | Included | |
| <u>Reducing Gear</u> | | |
| Manufacturer | | |
| Type or Model | | |
| Reducing Ratio | | |
| Eff. at Full Load, % | | |
| <u>Control</u> | | |
| Local Control Panel | Included | |
| Control Hierarchy | PLC is connected to CPLC of the WWTP | |
| Environment | Corrosive Atmosphere | |
| Material | SS316 | |
| Ingress Protection | IP55 | |
| Values to be sent to HMI | Centrifuge on/off | |
| | Bowl speed, RPM | |
| | Motors power consumption, kW | |
| | Motors current consumption, A | |
| | Motors Temperature, °C | |
| | Feed flow rate, m3/hr, Optional | |
| | Polymer flow rate, m3/hr, Optional | |
| | Motors operation hours | |
| Alarms | Overheat | |
| | Overload | |
| | Vibrations | |
| <u>Decanter Centrifuge VFD</u> | | |
| Manufacturer | ABB, Vacon or approved equivalent | |
| IP rating | IP 54 | |

| Item | Minimum requirement | Guaranteed value |
|----------------------|---------------------|------------------|
| Operation conditions | Heavy Duty | |

1.14.11.3 FAT (Factory Acceptance Test)

After complete manufacturing of the equipment, the contractor shall notify the client that all the scope of supply has been checked in accordance with the equipment at the factory, and add a signed document for the factory acceptance test.

1.14.11.4 Running

The running will be performed in the presence of the manufacturer representative according the following procedure:

1. Dry run
 - i. The manufacturer representative shall approve the installation of the equipment and shall provide a signed installation report.
 - ii. Dry run after electrical connection of the equipment in order to validate proper operation of the centrifuge and that there are no vibrations and irregular noises.
2. Trial run with digested sludge
 - i. Running with digested sludge for 50%, 70% and 100% of the design load.
 - ii. The trial run shall be carried out for three (3) days. During the trial run the proper operation of the centrifuge will be tested, synchronization with the control system and obtaining the demanded dewatered sludge dryness.
 - iii. After the first trial run, the decanter shall be run by the WWTP staff for 60 days. The run will be complete after 60 days of continuous proper operation.